

TABELA ROBÓT ZIEMNYCH
 obiekt : Przebudowa ulicy Ślężoujście km 0+000 - km 0+498

		Wartości w przekrojach		Objętości	
Kilometraż	Odległość	Wykop	Nasyp	Wykop	Nasyp
km	m	m2	m2	m3	m3
0+000.00		3.30	0.00		
0+025.00	25.00	4.20	0.00	93.8	0.0
0+031.71	6.71	4.10	0.00	27.8	0.0
0+050.00	18.29	4.24	0.00	76.3	0.0
0+070.00	20.00	11.80	3.28	160.4	32.8
0+075.00	5.00	40.70	47.72	131.3	127.5
0+100.00	25.00	36.79	45.67	968.6	1167.4
0+125.00	25.00	39.34	54.43	951.6	1251.3
0+140.00	15.00	45.50	60.66	636.3	863.2
0+175.00	35.00	80.61	89.50	2206.9	2627.8
0+187.25	12.25	107.07	125.33	1149.5	1315.8
0+195.00	7.75	111.62	128.98	847.4	985.5
0+199.00	4.00	107.13	130.22	437.5	518.4
0+225.00	26.00	101.15	106.05	2707.6	3071.5
0+250.00	25.00	120.79	132.93	2774.3	2987.3
0+275.00	25.00	114.40	127.82	2939.9	3259.4
0+300.00	25.00	111.20	116.82	2820.0	3058.0
0+325.00	25.00	66.80	58.82	2225.0	2195.5
0+350.00	25.00	41.50	48.29	1353.8	1338.9
0+375.00	25.00	37.09	42.47	982.4	1134.5
0+386.00	11.00	52.11	43.97	490.6	475.4
0+389.00	3.00	47.38	41.72	149.2	128.5
0+394.00	5.00	3.60	5.19	127.5	117.3
0+400.00	6.00	4.23	2.26	23.5	22.4
0+425.00	25.00	5.52	0.72	121.9	37.3
0+450.00	25.00	4.17	0.48	121.1	15.0
0+475.00	25.00	4.74	0.00	111.4	6.0
0+495.00	20.00	3.18	0.00	79.2	0.0
0+498.00	3.00	4.20	0.00	11.1	0.0
		R A Z E M		24 725.76	26 736.43